

Work Book

LANGLEY FLOW

Table of Contents

1. **Introduction & Vision**
2. **Site Analysis**
3. **Concept Development**
4. **Design Principle**
5. **Green Infrastructure Development**
6. **Path Network Developmet**
7. **Precedent studies**
8. **Housing Concepts**
9. **Masterplan**
10. **Planting Strategy**

1. Introduction & Vision

Site Summary & Development Context

Langley SUE is located in north Birmingham, adjacent to Sutton Coldfield and New Hall Valley Country Park. It spans 274 hectares and is expected to deliver 6,000 homes. This growth responds to Birmingham's housing need and future population growth projections. The site benefits from access to the A38, M42, and proposed Sprint transport systems, placing it in a well-connected urban growth corridor.

This workbook introduces the concept of "**Langley Flow**" - a visionary, blue-green infrastructure-led framework that reconnects people with nature through water-sensitive design, ecological corridors, and healthy mobility networks.





Planning Context

Covered under Policy GA5 in the Birmingham Development Plan.

Guided by the SPD to create a healthy, well-connected, and green community.

Focuses on land use, housing mix, transport, and long-term public space care.

Langley is one of the largest housing allocations, released from the Green Belt to support Birmingham's need for 51,000 new homes by 2031.

Strong focus on sustainable travel, with future access to HS2, city routes, and transit hubs.

Part of Birmingham's wider strategy to create thriving, low-carbon neighbourhoods.





Source : Birmingham City Council

2. Site Analysis

Site Visit

1.

2.

3.

4.

5.

6.

7.

8.

9.

These site moments — hedgerows, brook edges, horses, and standing water — shaped Langley Flow. They reminded me the land needs continuity, not disruption.



Site Analysis

Topography & Elevation

At the Langley site, the ground is never steep and there are areas that are flat and arable, along with some elevated zones. Because the ground slopes in a natural way to the Langley Brook and the small pond hollows, the site collects water into a tiny catchment.

These subtle elevation differences provide key design opportunities: higher ground can support residential or public realm development, while lower areas are suitable for flood retention, wetlands, and green corridors.

Understanding this gradient is essential for planning stormwater flow, visibility lines, and connectivity between habitats.





Soil & Drainage Conditions

The land above is made of clay and sand/gravel, while the bedrock is made of mudstone.

It is hard to drain the soil because it is clay – proper management is important.

Bioswales, permeable paving and improved soil all limit the amounts of runoff and soil erosion.

For this kind of soil, choose plants such as field maple, willow and wildflower meadows.





Hydrology & Flood Risk

The site contains eight existing ponds, several ditches, and Langley Brook, which flows through its eastern boundary. However, current water bodies are fragmented.



Parts of the site lie within flood-prone zones, particularly adjacent to the brook.



By linking ponds and creating a sequence of retention basins, the design can support a self-sustaining water system while reducing flood risk and enhancing microhabitats.

Vegetation & Tree Cover

Langley's existing vegetation :

- Semi-improved grasslands
- Scattered scrub
- Woodland
- Patches of broad-leaved plantations.

Tree cover is generally sparse and uneven

Opportunities:

-More connected green canopies

Existing trees:

-Influence microclimate

-Shaded pedestrian path

-Cooling buffers

-Visual screenig between zones







Sun Direction

North side do not get any direct sunlight.

Windows placed in the Northern direction will get more natural light.

South and West side gets the maximum amount of sun that heats up the place quick.

Therefore,

North - Huge windows for natural sunlight penetration.
South - Could be provided with sun barriers to reduce heat.



Source: https://andrewmarsh.com/apps/staging/sunpath3d.html

Hedgerows & Ecological Connectivity

Langley contains a mix of intact, defunct, and unmanaged species-rich hedgerows, most of which run parallel to field boundaries and foot-paths.

1

2



Solitary Bees

"As well as being beautiful to look at, wildflowers are great for biodiversity by providing pollen and nectar for pollinating insects and also acting as 'wildlife corridors', allowing insects and other invertebrates to thrive. Large areas of wildflowers such as those we will be planting in Sutton Coldfield can be beneficial in raising air quality, as they remove a range of pollutants from the air.

There has been a sharp decline in bees, butterflies and pollinating insects over recent decades and, like most people, as a Council we are alarmed by this. We're determined to protect and improve Sutton Coldfield's natural environment and this fairly simple change to how what-is-currently-roadside-grass is managed will help increase the habitats and food that our pollinating insects rely on." - Councillor Clare Horrocksw



Historic Change, Habitat Fragmentation & Ecological Targets

For 140 years, changes have taken place at the Langley site. According to maps made in 1880, England had many more hedges and woods, most of which no longer exist due to farming and housing development.

The cover of woodland has decreased on the site, causing both the canopy and wildlife corridors to shrink. Therefore, I suggest restoring all hedgerows and woodland belts to link conserved habitats and promote diversity in the area I live in.

The same recommendation is given by national agencies:

1. The Committee on Climate Change (2019) proposes that by 2050, hedgerows in the UK should be increased by 40 percent.

2. According to the Woodland Trust, the rise from 13% to 19% in woodland area can lead young native woodlands to remove over 400 tonnes of carbon from the environment per hectare.

On-site, I will design taking into account the targets mentioned above.

1. Improving old hedgerows and restoring those that are not working anymore

2. Building corridors containing both species of shrubs and trees

3. Growing the number of native forest groups

4. All newly planted trees should benefit pollinators and nesting birds and also increase the area's resilience to climate change

Langley's blue spaces remain fragmented, and pond distances (often over 100m apart) limit amphibian breeding — particularly great crested newts. Addressing this in my masterplan will involve improving pond spacing, linking wetlands, and integrating green-blue networks across the site.



Road & Access Network

The A38 highway runs diagonally from southeast to north-east, forming the eastern boundary of the site.

Internally, two minor roads structure the site:

1. Fox Hollies Road enters from the southwest corner and travels diagonally toward the central part of the site.

2. Ox Leys Road approaches from the west, intersecting Fox Hollies near the site's center

The external road network supports access to nearby neigh-bourhoods:

Webster Road, Thimble Road, and Springfield Road run north–south through the southern neighbourhoods, offering future pedestrian and local vehicle connections



Site Access Points

The identified access points from north to south include:

1.Springfield Road, opposite the Kingdom Hall of Jehovah's Witnesses (B75 7JJ)

2. Ox Leys Road

3. Springfield Road, opposite Berryfields Road

4. Signal Hayes Road

5. Fox Hollies Road

6. Webster Road

7.Walmley Ash Lane, near Footsteps Walmley Nursery & Pre-School (B76 2AA)

Demographics

Older Adults (50–69 yrs):
Design must include accessible paths and age-friendly spaces.

Children & Teens (0–19 yrs):
Over 21,500 residents schools, play areas, and safe public spaces are essential.

Young Adults (20–39 yrs):
Smaller group but growing



Source: https://www.citypopulation.de/en/uk/westmidlands/admin/birmingham/E04012653__sutton_coldfield/

Ethnic & Social Mix:
Diverse population - need for inclusive, adaptable spaces



Loneliness Risk:
Most areas low risk, but pockets of high isolation exist public realm must promote social interaction and community hubs.



Currently moderate pollution; risk of NO_2 & PM10 increase - need for green buffers and low-traffic zones.



Source : Birmingham City Council





19.5% of people in Sutton Coldfield are linked to the health risk register. The percentage is (vs 13.9% in UK, 12% in Birmingham) times higher; let's use design that benefits health.

Public Transport

Public transport plays a crucial role in reducing congestion, emissions, and car dependency. The Langley site is already surrounded by well-served bus routes and within cycling distance of a major train station.

There are multiple bus stops around the site's perimeter, with regular services to:

- Birmingham city centre

- Sutton Coldfield

- Tamworth

- Walsall

Springfield Road and Thimble End Road stands out as a key transport spine.

The nearest train station is Sutton Coldfield, just:

14 minutes by bike

42 minutes on foot
(Approximately 1.8 miles from the junction of Springfield and Ox Leys Road)



SWOT Analysis

STRENGTH

- Location – Right next to Sutton Coldfield, with access to the A38 and other strategic roads.
-
- Mostly open space – 274 hectares gives us a chance to design from scratch, with green infrastructure at the heart.
-
- Existing natural features – Hedgerows, ponds, and Langley Brook offer ecological and design value.

WEAKNESS

- Clayey soil and poor drainage , Makes water retention and planting harder without intervention.
- Disjointed access, Few internal routes, vehicle and pedestrian movement needs planning from zero.
- Sparse vegetation cover – Not much tree canopy, so limited microclimate benefits at present.
- Fragmented ponds and green spaces – Ecological corridors are broken, reducing biodiversity.

THREATS

- Pressure from development – Risk of overbuilding or fragmenting green spaces.
- Flooding potential – Especially near Langley Brook if not managed well.
- Traffic congestion – Without clear mobility planning, reliance on cars could increase.
- Biodiversity loss – If hedgerows and ponds are not restored and protected, habitats may disappear.

Opportunities

Concept Development

Langley Flow

Langley is designed as a place where people, nature, and water thrive together, with homes built around green corridors, connected ponds, and walkable paths that bring the community closer to each other and the land they live on.

Rather than zoning nature to the edges, Langley Flow pulls it inward into back gardens, footpaths, and daily routines.

Design Principle

Langley Flow is built around a system of layers — each serving a different function but designed to work together.

The blue layer carries water — connecting ponds and managing stormwater.

The green layer connects hedgerows, meadows, and trees — forming wildlife corridors and shaded routes.

The movement layer weaves safe pedestrian and cycle paths between homes, schools, and transit points.

These layers intersect at key moments to form shared spaces, community nodes, and ecological hot spots.



Restore Biodiversity

Use layered planting, restored hedgerows, and seasonal species to bring life back to the landscape.



Reconnect Water Systems

Link ponds, brooks, and ditches into a continuous water network that filters, stores, and supports habitat.



Support Community Life

Ensure every home is within walking distance of a park, a school, a shop, and a place to meet people.



Promote Active Mobility

Design for walking and cycling first—safe, green, shaded, and separate from cars.

Imagine standing at the edge of Langley on an autumn morning.

The hedgerow beside you rustles with life.

A path leads past tall grasses, where bees hover around blooming goldenrod.

You pass low shrubs — colourful in spring, textured in winter

and come to a clear pond where birds skim the surface.

A wooden deck invites you to pause.



Walk, Cycle, Pause — Repeat

At Langley, movement is more than getting from A to B. It's part of how we live better

That's why walking and cycling aren't an afterthought. They're built into the very bones of the plan. Routes are:

Shaded by trees in summer

Lined with pollinator plants

Interspersed with resting spots with views over ponds

School children can walk along wildflower-lined paths. Residents can ride safely to Sutton Coldfield. Older adults can sit on a bench near a bee-friendly border

Green infrastructure development

Existing Green Assets & Site Potentials

Key existing features include:

1. Intact Species-rich Hedgerows

2. Defunct Hedgerows

3. Scattered and Dense Scrub

4. Semi-improved Neutral Grasslands

5. Eight Ponds (fragmented but vital aquatic habitats)

Nature is already here. The task is to make her whole again.





Analysis of both the existing hedgerow map and historic mapping, we can see how once-continuous ecological corridors have become fragmented over time.





By tracing the pre-1880 field patterns visible in historic maps and cross-referencing them with intact and species-rich hedgerows still visible today, hedgerow restoration can be done in these places on site



Areas prioritized for retention and enhancement, with opportunities mapped alongside the 1880 historic hedgerow overlay

Green infrastructure baseline without hedgerow layers

Path Network Development

Precedent Study : Milton Keynes Redway System, UK

The Redway Code – Respect, Protect, Enjoy.

The Redways are an important part of Milton Keynes. They are shared-use routes for people on foot or on cycles. The traffic-free network is popular for leisure, for commuting and for staying active. Redways may be used by anyone cycling and walking including people with pushchairs or prams and those in wheelchairs (including powered wheelchairs / mobility scooters). To enjoy them, please follow these common sense guidelines.

Throughout Milton Keynes, the Redway System consists of many miles (over 200, in total) of shared paths for cyclists and pedestrians. Opened in the 1970s, these paths covered in red are next to main roads and run inside parks, giving people in the city protected traffic-free places to walk. The area provides underpasses and bridges, ensuring that active transport is possible and important within the urban arrangements.

Source : https://www.destinationmiltonkeynes.co.uk/getting-around/maps/

Learnings for Langley:

Dedicated, safe pathways for non-motorized users

Integration with natural landscapes and urban areas

Long-standing example of successful active transport infra-structure

Path Network Development



Made initial sketch exploring road loops and cycle path alignment, setting the ground-work for a connected, low-traffic landscape.

- Langley's road system has been designed to provide essential vehicular access without compromising the core principle of a walkable, cycle-friendly community.

- The idea is not to eliminate cars, but to control and contain their presence.



Primary Vehicular Movement

The road network features four circuits (Fox Hollies, Ox Leys, Walmley, Lindridge) with new emergency and service access, maintaining ecological areas.

Loop 1 – NW Circuit (5.5 km):
This loop ties together the northwest area through Fox Hollies and Springfield Road, bypassing the green core. It's vehicle-friendly and bypasses the vulnerable central section

Loop 2 – South West Circuit (3.74 km):
There is a loop at Fox Hollies that links school traffic as well as Ox Leys Road dwellers to Walmley Road. The most crucial stretch from Walmley to Fox Hollies stands at approximately 1.77 km.

Loop 3 – South East Circuit (2.66 km):
The southeast contains ponds, orchards, and meadows. This loop provides improved access, equalizes maintenance, and reduces fragmentation in restoration zones.

Loop 4 – North East Perimeter Loop.
A corridor along Fox Hollies Road and in nearby areas diverts heavy traffic, enhancing regional flow and safeguarding the countryside.

Primary Vehicular Movement



Loop no.	Roads Incl.	Length	Area served
1	Fox Hollies, Lindridge, Springfield	5.5 km	NW
2	Fox Hollies, Ox Leys, Walmley	3.74 km	SW
3	Fox Hollies, SE Ox Leys, Walmley	2.66 km	SE
4	Lindridge, Holly Lane, Ox Leys	4 km	NE

Master sketch of proposed vehicular spine road network — illustrating four connected loops that provide essential site access

Cycleway Network Strategy

After defining the primary road loops, the next step was to create a cycle and pedestrian network that gives people safe, beautiful, and direct ways to move around Langley without needing a car.

Most cycle and walking paths are intentionally aligned with the main vehicular loops — but they offer a much richer experience: passing through woodlands, tracing the brook, and winding through orchards and meadows.



Not to scale

Concept cross-section of Fox Hollies Boulevard — balancing vehicle flow with generous, green pedestrian paths.

Cycle & Pedestrian Loops

Loop 1 – Brookside Circuit (4.5 km):
Follows the Langley Brook, the extended Fox Hollies Road, and weaves through green corridors. This loop acts as a linear park experience — cool, shaded, and full of biodiversity.

Loop 2 – Woodland Edge Circuit (3.1 km):
Sits just beside Loop 1 and hugs the edge of buffer woodlands, creating a slightly more enclosed trail. Great for both walkers and cyclists looking for calm green space.

Loop 3 – Upland Garden Loop (Approx. 2 km):
A tighter loop above the previous two, connecting through higher ground and orchard planting areas. Ideal for shorter, everyday trips within residential clusters.

Loop 4 – Southern Woodland Trail (2.5 km):
Enters from Walmley Road and moves through the southern woodland belt. This loop is perfect for early morning jogs, quiet evening walks, and school commutes through nature.



Proposed network of pedestrian and cycle loops

Brook side cycle/ Walk

Transition zone from woodland

Boulevard cycle/Walk

Woodland cycle/ Walk

Conceptual collage

Precedent Study

South Bronx Greenway, New York, USA

Key Features :

Pedestrian & Cycle Connectivity

1. Introduced 11+ miles of continuous greenway for non-motorised movement
2.Safe, segregated bike and pedestrian lanes along key roads and waterfronts

Environmental Benefits

1. Native plantings reduce urban heat island effect
2. Stormwater infrastructure (bioswales + permeable pavements)

Health Benefits

1. Designed in collaboration with local residents
2. Connects schools, parks, and commercial areas
3. Supports active travel and improved air quality in a previously over-industrialised zone

Public Realm Improvements

1. Pocket parks, shaded rest points, fitness areas
2. Public art installations and local cultural integration
3. Wide pathways with materials suited for walking, cycling, and accessibility

https://culturenow.org/site/south-bronx-greenway-master-plan

Relevance to Langley SUE

Greenway Structure

- This has an analogy with Langley's idea of a looped path network, as SBG shows how non-vehicular loops can be fully continuous to merge homes, schools, parks, and health hubs.
- Langley Application: Reinforce looped cycle/pedestrian circuits around ponds, woodlands, schools, and civic zones.

Stormwater Management Integration

- Bioswales and permeable materials thus synergize with Langley's green infrastructure aim alongside active mobility.
- Langley Application: Let cycle paths track along the bioswale/ hedgerow corridors and retention ponds.

Human-Scale Design

- Wide paths, with benches, lighting, and shade, invite walking and cycling on a daily basis.
- Langley Application: Design cycle/pedestrian loops with rest zones, edible hedgerows, and wayfinding.





https://culturenow.org/site/south-bronx-greenway-master-plan

City Planning by Le Corbusier (area11,400 hectares)

1. 7V Road Hierarchy Model
Concept: Roads categorized from V1 to V7 for controlled vehicular and pedestrian flow.
Application to Langley SUE:
Segregate vehicle and non-motorised transport.
Plan zero-traffic residential areas.
Dedicated cycling and pedestrian corridors for safety and sustainability.

2. Self-Sufficient Sectors
Concept: Walkable sectors with integrated services — schools, parks, shops, and clinics.
Application to Langley SUE:
Embed the "15-minute city" idea.
Promote community interaction and local economy.
Reduce reliance on private transport.





3. Integration of Nature – Green Ring
Concept: Peripheral greenbelt for ecological integrity and urban containment.
Application to Langley SUE:
Introduce green buffers and corridors.
Restore hedgerow connectivity and ponds.



Source : https://www.townandcountryplanninginfo.com/2020/09/chandigarh-city-planning-by-le-corbusier.html

Bishan–Ang Mo Kio Park, Singapore

Soil Bioengineering for Riverbanks:
Use vegetation and natural materials to stabilize hedgerows and pond edges.

Connecting Green Infrastructure with People:
Remove physical boundaries (no fences).
Increase walkability and access from adjacent neighbourhoods like Sutton Coldfield.

Recycling Materials for Landscape Features:
Reuse construction waste (bricks, broken concrete) for pathway edges or benches.
Incorporate natural elements like logs or scrap wood for bee hotels and play zones.

Wetland-based Rainwater Purification:
Introduce vegetated pond systems for runoff purification.
Encourage a self-sustaining water cycle within pond habitats.



Takeaways for Langley

Idea	Chandigarh	Bishan Park	Langley – How It Can Use the Idea
Planning and layout	City is divided into sectors	Area for play and walking	Plan separate areas Such as – Nature, people, no traffic zone
Water Use and Management	Straight concrete canals	Natural streams with plants	Make ponds with plants to treat the water being collected
Green Space	Tree lined roads and parks	Green park flows through the city	Connect vegetation with trees, hedges, grass, meadows etc.
Focal point	Famous building	River is the main feature	Have a focal point on site
People and Nature	Public parks and open space	Spaces for walking and playing	Integrate sign boards to teach about nature

Design Development

Key Design Features on Site

Therapeutic Garden & Health Hub: Situated near woodlands to foster calmness and healing.

Fox Hollies Boulevard: Designed as an active green spine with bioswales, and dedicated cycle routes.

Vernal Pond & Wet Meadow Park: A seasonal landscape supporting biodiversity and water management.

Glasshouse Garden: A flexible indoor/outdoor botanical zone for education, local food, and events.

Meadow Park & Woodland Buffer: Framing development with native planting, sound mitigation, and wildlife support.



Therapeutic Garden Concept

A sensory-rich green space adjacent to the health hub, designed for mental well-being, passive healing, and gentle interaction with nature.

Conceptual plants for therapeutic garden :

Chamomile
(Chamaemelum nobile)

Hawthorn
(Crataegus monogyna)

Dandelion
(Taraxacum officinale)

Water Mint
(Mentha Aquatica)

Source: https://totallywilduk.co.uk/

Tiered Garden (Serralves-Inspired)

Inspired by the geometry and flow of Serralves Gardens, this layered landscape integrates wetland meadows, vernal ponds, woodland edges, and a central viewpoint.



Glasshouse Garden Concept

Design Development Precedents

Picasso Food Forest - Edible Landscapes, Parma, Italy

Initiated in 2012, the Picasso Food Forest transformed a neglected urban area into a thriving community-managed edible landscape, promoting social cohesion and environmental education.

Key Features:

Community-Led Initiative: Developed and maintained by local residents, emphasizing grassroots involvement.

Educational Programs: Provides learning opportunities about sustainable agriculture and biodiversity.

Environmental Benefits: Enhances urban biodiversity and offers ecosystem services like air purification.

Relevance to Langley SUE:

Urban Renewal: Repurposing underutilized spaces into productive landscapes can revitalize communities.

Educational Integration: Incorporating learning spaces within edible gardens can promote sustainability awareness.



Source : https://www.fruttortiparma.it/foodforest_en.html

Housing Strategy : Precedents

The Fleet / Hithe – Ebbsfleet Garden City

A riverside urban form with fine grain development and mixed-use housing.

Key takeaways for Langley Zones 5 & 6:

Blocks aligned along contours maintain views and permeability.

'Fleets' or water inlets act as public spaces.

High-density homes with active ground floors and compact street design.

Strong east-west and north-south axes improve walkability.



Source: Ebbsfleet Garden City

Marmalade Lane – Cambridge

Overview: A 42-home multigenerational cohousing community in Orchard Park, Cambridge.

Features:

Mix of apartments and townhouses.

Central ‘Common House’ with shared kitchen, dining area, laundry, and guest rooms.

Shared gardens and pedestrian-friendly lanes.

Developed through collaboration between future residents, the local council, and developer TOWN.

Insights: Highlights the importance of resident involvement in the design process and the benefits of integrating communal spaces to foster community interaction.



Source: https://propertycollectives.com.au/

Cottage Clusters for Aging-in-Place – Propel Studio, USA

Designed for affordability, barrier-free access, and shared green space.

Key takeaways for Langley Zone 2:

Single-storey homes with shared gardens.

Communal walkways and driveways placed at edges

Gardens could capture rainwater

Communal living without the need for institutional care.

Source: Propel Studio

Housing Concepts for Langley

Zone 1A & 1B – Townhouses



Zone 2 – Cluster Housing (Cottage-inspired)



Zone 3 Marmalade-Inspired Urban Terrace

Zones 5 & 6 – The Fleet Housing

Conceptual Model : Fleet Houses (Langley Brook)

Draft Masterplan



A shared growing and gathering space at the heart of the northern neighbourhood, framed by woodland and housing.

Fleet Houses (Near Brook)

Restored Langley Brook with vegetated edges

Pollinator meadow park centrally located provides biodiversity value and visual relief

A large stormwater pond feeds into the brook — enhancing flood control, habitat, and landscape identity.

Centrally placed for walkable access shared playgrounds bring together all ages to play and connect.

Inspired by Serralves Gardens , this landscape blends seasonal ponds, wet meadows, and stepped seating decks.

Four 6m-wide vehicle loops around habitat cores

Townhouses

Bordering woodland and housing, this space supports year-round growing, workshops, and quiet retreats.

Secondary cycle and pedestrian paths with four loops

Masterplan 1:500 Therapeutic Garden & Communal Parking



Masterplan 1:5000



Planting Strategy

February

Acacia dealbata	
Winter flowering cherry	
Salix caprea	

March

Corylus avellana	
Prunus spinosa	
Prunus domestica	

April

Acer campestre	
Malus sylvestris	

May		June		July	
Acer pseudoplantanus		Common lime		Sweet Chestnut	
Hawthorn		Hop tree		Indian Horse Chest nut	
Holly					